

## Efficient Site Design

By: Dale Stacey

dale@satpty.com



### Synopsis

The greatest spend in establishing new mobile radio/telecommunication sites is invariably in the real estate, the access, civil works, and establishment of tower/building structures and power. Experience shows that this can equate to >90% of the capital cost. So why is this part of the project so often poorly considered in our build of radio infrastructure projects? This presentation deals with some lessons learned, oversights and pitfalls in establishing sites and some future strategies and building checklists to capture fundamentals of what we need.

- regulations governing site builds
- concept of right sizing
- number of sites growing
- concept of the value of a site and tower in real estate terms
- remoteness multiplier
- building site and tower structural survey databases
- practical trumps theoretical
- impact of increasing regulation (tickets, inductions, grinding pegs off, fencing)
- increasing environmentalism (managing aesthetics, radiation to public)
- checklist for site surveys



## Disclaimer

These are my views, all care no responsibility ! no one can be an expert on everything !



## Inherent Value of a Site / Tower

a) It is Commercial Real Estate with an inherent commercial value (Value = x times the annualised RoR after costs), typically x will be 5.

b) Value function of Captive market, location, (High Density to Remote bit like ACMA rates).

c) Exclusivity (ie is there only one site available).

d) Supply/Demand.

e) Coverage Profile.

f) Access.

g) Amenity (suitability for what you are trying to achieve). (Is it easy Landlord to deal with etc)

h) Facility (Is the tower suitable with capacity, is the equipment room suitable, is the Power supply and HVAC suitable with capacity)

i) Trade off between Lease rather than own and operate

SAT have built a database valuing sites to aid carriers when assessing the value of a site (Value a+b+c+d+e+f+g+h+i), (done this twice.)



## (MAIN) Regulations governing site builds

#### WIND LOADING / STRUCTURAL DESIGN

-AS 1170 Code upgraded in 2011, again in 2021

-2011 the windloading parameters became more stringent from previous

-2021, (new wind region maps, region B and C have increased in size),

(C cyclonic and D extreme cyclonic)

This theme is likely to continue with recent Global events.

#### STEEL DESIGN

-AS 3995- Design of steel lattice towers and masts

#### **CONCRETE DESIGN**

-AS 3600: 2018 Concrete Structures, Steel & Tendons

#### ELECTRICAL DESIGN

-AS/NZ 3000 - The Wiring rules

-AS 3010.1 Generating Sets.

-AS 45091 Australian Skills Qualification

#### GUIDELINES

-issued by Clients. (Optus, Telstra, State Governments) -Sustainability requirements (Power, disaster withstanding/ recovery)

#### MANDATORY OHS

Climbing, Safety, Fencing, increasing Public awareness, ARPANZA

## WIND REGIONS AUSTRALIA





## General Concept of Optimising / right sizing / Minimisation / Value Engineering.

#### www.satpty.com

Sizing the tower height - (polynomial cost as a function of height), LOS, coverage delimited, consider reducing height, access, alternate tower type

Sizing the power can easily have quadruple to 10 fold ripple effect cost (6-10 dB cost in radio speak)

Earthing, lightning protection considerations

Power, Critical point at which uneconomic to connect to grid, definition of a solar site

Access and serviceability costs (track)

Capex versus lease.

Dissipating heat

Optimising indoor/outdoor mix of equipment (move to outdoor) (example 5G technology)

Getting rid of PIM

Serviceability

Reliability Calc

TOTAL COST OF OWNERSHIP MODEL/ANALYSIS.



## **Electrical Design**



## The Ripple Effect -Example

#### Adding 6 extra channels could add

~2 KW peak load onto the Power system  $\Rightarrow$  requiring addition Battery capacity  $\Rightarrow$  Power AC to DC Power upgrades  $\Rightarrow$  heightened max demand  $\Rightarrow$  additional cooling  $\Rightarrow$  Transformer upgrade  $\Rightarrow$  Transmission Line upgrade

In limit 5 x the Peak Load capacity (note doesn't account for site autonomous Power systems which can be much greater cost)

Equipment Load	AC/ DC Power Supply upgrades	Equipment Room Cooling upgrades	Max Demand upgrades add 10 kVA	Transformer upgrades	LV or HV Line upgrade
~Peak 2 kVA	Add charging ability 60A at 48V=~3kVA	Add Max~5kVA		415/11,000V Upgrade by 10kVA	Maybe needs upgraded
1500 kVA		Main 16 hrs, second	2		
Power consumption typically 400-500W per		summer 8 hrs day, DC fan 8 hrs winter less (30			X
channel 2kW for 6 channels +		KWhr) EER (high 3's)			
peripherals (router, microwave)					
6100					



## Real Cost of Power System Provision



www.satpty.com

Equip	\$100K	\$100K	\$100K	\$100K	\$100K
DC Power Supply upgrades		\$25K	\$25K	\$25K	\$25K
Cooling upgrades			\$15K+\$15K	\$15K+\$15K	\$15K+\$15K
Transformer Upgrades				\$50K	\$50K
Power Line upgrades (example 2Km's)					\$300K
running total	\$100K	\$125K	\$155K	\$205K	\$505K



Operating Expenditure (Opex)

www.satpty.com

2kVA load equates to 2.2 x 24 x 365 kWhr/year = 19,272 kWhr or \$3854.40 per year (as 20c a kWhr) RAW LOAD

Max Load ~10kVA

~ADMD load is more like 4kVA ~ \$7708.80 per year (as 20c a kWhr) aggregate system

(typically 2-10 times a domestic bill) - Not insignificant, not environmental.



## Load Minimisation

www.satpty.com

How can we reduce the electrical load at a site.

- -strip out whats not required (lights, auxiliaries, overkill Hot Standby Duality)
- -Smart management of devices (turn on and off, pick charging times)
- -Optimise with duty cycles / batteries /(solar)
- -Build to demand not excess. (modular if necessary)
- -Optimise and minimise cooling cycles, fans not A/C etc
- -Location of equipment out of the sun with passive cooling skins/double skins
- -Move Loads outside (growing theme with 3G/4G/5G and link ODU, all outdoor)



Winter / Alpine Climates

www.satpty.com

-As lots of sites are top of mountain

-trickle heat (maybe use the residual heat from the equipment)

-retain passive heat

-minimise airflow



## Break even point between grid power and off site

Cost where TCI over x years is better than cost of connect plus kWhr expectation

-typically a 10 year TCI analysis +/-

-Derive a table of kWhr total cost versus off site and minimise as per previous steps

- . \$200-300k not going to buy much... or unusual
- . <sup>3</sup>⁄<sub>4</sub> of a Kilometre is a benchmark of sorts (cost of extending a 11 KV line in Victoria 300k in todays costs)









## Earthing and Lightning Protection

#### www.satpty.com

Protects People and Equipment

To define the nature of a LPS

-IEC 62305 risk assessment

-Soil resistivity

-Good Housekeeping, Earthing kits applied

top bottom, bends and into equip room (plus 10m intervals)

-No loops bond. Separate Comms and Electrical Earths





## Equipment Room Design

#### www.satpty.com

Continuing the Example from above. Where do we put all this 'stuff'

Our Outdoor half size 19' equipment rack (600 x 600 x 1100)	FOOTPRINT 1 m <sup>2</sup> VOLUMETRICALLY = 0.596 m <sup>3</sup>
Include plinth 1000 x 1000 x 200	
$\frac{1}{2}$ x 19' rack for Mobile Radio Base station (600 x 600 x 1100)	FOOTPRINT 9m <sup>2</sup> VOLUMETRICALLY = 14.4 m <sup>3</sup>
1 x 19'rack for Power Supply System and batteries (600 x 600 x 1100)	
= equipment room, minimum 2400 x 2400 x 2400 (for erganomics)	
-concrete plinth to support equipment room (3000 x 3000 x 200)	
Outdoor area for mounting 2 split air conditioners (typically 600 x 600 x 300 each)	

Ie Footprint increase ~900%, Volume increase ~2300%



## Real Estate

www.satpty.com





## Lattice Tower Installation





## Spun Concrete Pole Build





*	
www.satpty.com	
-SpaceGas	
-SAP	

-Atena

-Tekla

-Bentley

-CheckPole

-RocPole

-Finite analysis/Calculus based.

Pre loaded codes and antenna systems

**Tower Modelling** 





## Dimensioning a Tower

#### www.satpty.com

- -Height requirement
- -Strength and loading requirement
- (Antenna Matrix)
- -Locating
- -Foundation Design
- -Installation
- -Feeders
- (ancillaries Hut, Power, Fence..)









Extract from

SAT Database

**BENCHMARKING COSTS** 

60 Sites with

detailed build cost





## Mix Easy / Medium / Hard / Extreme

#### www.satpty.com

Extract from

SAT Database

60 Sites with

detailed build cost







## Bands pre 2011, 2011-2019, Post 2019

#### www.satpty.com

Normalised

Extract from SAT Database

60 Sites with detailed build cost

-CPI multiplier applied

-Normalising Multiplier of 2.11

applied pre 2011

-Normalising multiplier of 1.09

applied 2011-2021.





## Breakdown of foundation / installation / tower hare ware costs

#### www.satpty.com

Height	Name	Foundations	Installation/Services	Tower Hardware	Tot Cost
25	нт	26.79%	29.56%	43.65%	\$ 201,588.00
25	R	20.31%	67.41%	12.28%	\$ 206,797.34
30	АР	26.34%	71.18%	2.48%	\$ 888,360.00
30	CL	16.63%	76.17%	7.21%	\$ 541,200.00
22	РМ	30.31%	64.98%	4.71%	\$ 468,600.00
25	TSWWTP	18.02%	77.08%	4.90%	\$ 498,960.00
30	Yar	6.68%	87.58%	5.74%	\$ 404,481.00
20	MtR	38.19%	45.93%	15.89%	\$ 277,585.00
20	MtP	43.22%	42.37%	14.41%	\$ 305,406.95
10	MtH	60.95%	18.53%	20.52%	\$ 126,896.00
25	Bertha	23.27%	65.41%	11.32%	\$ 337,634.00
20	CWWTP	7.87%	84.23%	7.89%	\$ 183,546.00
10	ST	46.23%	20.14%	33.62%	\$ 95,172.00
20	GD	5.61%	93.02%	1.37%	\$ 175,615.00



## Breakdown of foundation / installation / tower hare ware costs

www.satpty.com

Yellow = Tower Hardware \$32,319

Blue = Foundation \$81,772

Red = Installation \$210,275

60 tower average Medium tower height 21m Average cost = \$324,367





## Aesthetics

www.satpty.com



Increasing environmentalism (managing aesthetics, radiation to public)







### Checklist for site surveys



- regulations governing site builds
- concept of right sizing.
- number of sites growing.
- concept of the value of a site and tower in real estate terms.
- building site and tower structural survey databases.
- practical trumps theoretical.
- impact of increasing regulation (tickets, inductions, grinding pegs off, fencing)
- increasing environmentalism (managing aesthetics, radiation to public,)
- checklist for site surveys



Technology Improvements on Tower Loading E.g. Microwave

www.satpty.com

O	LD	NEW		
10%	ø3.7m antenna or above			
10%	ø3m antenna	5%	ø2.4m antenna or above	
20%	ø2.4m antenna	20%	ø1.2m antenna	
20%	ø1.8m antenna	25%	ø0.9m antenna	
20%	ø1.2m antenna	25%	ø0.6m antenna	
20%	Ø0.6m antenna	25%	ø0.3m antenna	

-Note benchmark for windloading of 3.0m antenna in australia in region a 3m = 20 kN (old AS 1170.2 code) Use area ratio to adjust this up and down

-Similar improvement in capacity (2 Mbps gone to ~400 Mbps, 200 fold, reliability up, LSI up)



# Collecting information at site survey

## **Developing Template**

SITE SURVEY FORM						www.satpty.com				
Summary										
SITE NAME:								ACMA ID or R	FSNA ID	
Date										
Ву										
Track General	Condition	A) 41	ccess Tr WD/2W	rack sui /D/Flat	itable for bed Truck/Cra	ne/Cor	icrete	Permissions / Keys required		
Site Location										
GPS LOG				Lat			Long		Comment	
Tower <u>Centre</u>										
Compound Ga	te									
Access Waypoi	int 1 (	)								
Access Waypoi	int 2 (	)								
Access Gate										
detailed GPS ac Structure Detai	cess log taker Is	n								
Structure type	D Building	Pole				Tower				
		wood	d Ste	el	spun	Lattic	e G	uyed		
					concrete			] 		
Manufacturer			N	1odel			IegL 4 legL			
Structure height	t	[		] (	taken with a laser )					
Access / Ladder	fitted	Acces	SS:				Ladder	Yes 🗆 No 🗖		
Fall arrest fitted		Yes 🗆	No 🗆	Manuf	acturer	Ma	del	Rati	ingkN.	
Last inspect		inspecte	ed			(	Current Yes/no			
votes umenity: :xpectation on Loading: :uitability for new antennas: :ondition of Tower / general Maintenance:										
Cable run:										



Documentation	and Phot	tos / Videos	
Documents to	Site Plan:	- Dian	
	Site Access Plan:		
	Compoun	d Invent	
	Eoundatio	n As built:	
	Towar Ar	huite	
	Tower Str	uctural Details:	
	Structural	Survey:	
	Tower Sho	op Drawines:	
	Equipmen	t Room Fixation:	
	Equipmen	t Room Lavout:	
	Electrical	Schematic:	
	Earthing 0	Diagram:	
	Antenna S	Schedule:	
	Feeder Sc	hedule:	
	Power Fee	ed drawings:	
	Solar Drav	vings:	
	Generato	r Drawing:	
	Geotechn	ical Assessment:	
Foundations / Guy		Completed	
Anchors inspected		Photograph any defects	
& Photographed		Comments:	
Climb structure		Photograph defects & label locations on tower elevation dwg	
& record all		Use Highest Resolution Practical	
defects		Completed	
in a separate		Comments:	
report			
Check condition		new/ just off colour / tarnished and weathered/surface rust/severe rust	
of galvanizing			
Check a sample		Check 5 random bolts on each face for tightness	
of bolts for		Completed L	
tightness		Comments:	
Check antenna			
locations against		Update tower elevations  (each antenna's to be shown only once on the elevations)	
orawings		Comments:	
Chark Antones		·	
/Feeders for		Dentry level in point missing elements/corroadd mounts/ torn radome covers/UUU earthing)	
defects /damage		Photograph any detects	
delects/damage		comments:	



Capture all	Photograph Antenna nameplate  (align antenna schedule & elevation dwgs)				
available	Update Antenna Schedule 🗆				
antenna details					
Check antenna	Provide updated info for RCSMB corrections (on the existing RCSMB document)				
against RCSMB	Completed				
Inspect lightning	Grounding kits fitted at top & bottom of all RF feeders				
protection	Surge arrestors fitted at gland plate				
	Gland Plate grounded to site earth				
	Highest point is a DC grounded Antenna or a lightning finial				
	Comments:				
Inspect	No corrosion/ mechanical damage/bolts are tight				
Structure	Completed				
earthing	Comments:				
connections					
Conduct a Site	As per Site earth test method provided (3 pole 62% method)				
Earthing test	Indicative reading (A) (Ohms)				
	(current probe at 20m & 50m from site boundary, voltage probe at 62% of current probe distance)				
	(10 km s state 100 km sto bundles)				
	Final test result (Ohms)				
	Pinal test result (Unms)				
Photograph	Via Drone				
Photograph each tower face	Via Drone (typ 3-5 photos progressing up the face including photos showing the complete face to allow scaling of antenna				
Photograph each tower face and tower leg	Via Drone (typ 3.5 photos progressing up the face including photos showing the complete face to allow scaling of antenna heights)				
Photograph each tower face and tower leg	Via Drone (typ 3 5 photos progressing up the face including photos showing the complete face to allow scaling of antenna heights) Completed				
Photograph each tower face and tower leg Photograph the	Via Drone         Operation           (typ 3-5 photos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed           Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site)         Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site)				
Photograph each tower face and tower leg Photograph the overall site	Via Drone         (hyp.3 s photos progressing up the face including photos showing the complete face to allow scaling of antenna heights)           Completed            Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site)           Completed				
Photograph each tower face and tower leg Photograph the overall site layout	Via Drone         (hy 3 - 5 photos progressing up the face including photos showing the complete face to allow scaling of antenna heights)         Completed         Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site)         Completed         Oppleted				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the solid is defined	Via Drone         (hy 3 5 photos progressing up the face including photos showing the complete face to allow scaling of antenna heights)         Completed         Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site)         Completed         Completed				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the cable ladder	Via Drone (typ 3 5 photos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed         Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site) Completed         Completed         Type of cable support fitted				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the	Via Drone       (typ 3 5 photos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate	Via Drone       (typ 3 - photos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed       Via Drone (at least 2 photos) taken directly above the structure center, encompassing the complete site)         Completed       Completed         Type of cable support fitted []         Completed       Via Drone (at least 2 photos) taken directly above the structure center, encompassing the complete site)         Completed       Type of cable support fitted []				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate All RF feeders are labeled at	Via Drone       (Ivp 3 - Sphotos progressing up the face including photos showing the complete face to allow scaling of antenna heights)         Completed				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate All RF feeders are labelled at the second	Via Drone (typ 3 5 photos progressing up the face including photos showing the complete face to allow scaling of antenna heights)         Completed         Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site)         Completed         Completed         Type of cable support fitted         Yes         Yes         Comments:				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate AII RF feeders are labelled at the gland plate	Via Drone (typ 3 5 photos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed         Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site) Completed         Completed         Type of cable support fitted []         Completed         Yes         No         Comments:				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate All RF feeders are <u>labelled</u> at the gland plate & antenna connection	Via Drone       (typ 3 s photos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed       Via Drone (at least 2 photos) taken directly above the structure center, encompassing the complete site)         Completed       Completed         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Yes       No       Image: taken directly above take				
Photograph each tower face and tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate All RF feeders are labelled at the gland plate & antenna connection	Via Drone       (typ 3 s photos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed       Via Drone (at least 2 photos) taken directly above the structure center, encompassing the complete site)         Completed       Completed         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Yes       No       Image: taken directly above the structure center, encompassing the complete site)         Yes       No       Image: taken directly above the structure center, encompassing the complete site)         Yes       No       Image: taken directly above the structure center, encomplete site)				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate All RF feeders are <u>labelled</u> at the gland plate & antenna connection Is there a Geotechnical	Via Drone (typ 3 sphotos progressing up the face including photos showing the complete face to allow scaling of antenna heights)         Completed         Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site)         Completed         Completed         Type of cable support fitted         Yes       No         Yes       No         Yes       No				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate All RF feeders are labelled at the gland plate & antenna connection Is there a Geotechnical assessment	Via Drone (typ 3 sphotos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed         Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site)         Completed         Completed         Type of cable support fitted []         Completed         Yes         Yes         No         Yes         Yes				
Photograph each tower face and tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate All RF feeders are labelled at the gland plate & antenna connection Is there a Geotechnical assessment Review latest	Via Drone (typ 3 s photos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed         Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site)         Completed         Completed         Type of cable support fitted []         Completed         Yes         Yes         No         Yes         Yes         No         Are all antenna included in the Structural assessment?				
Photograph each tower face and tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate All RF feeders are labelled at the gland plate & antenna connection Is there a Geotechnical assessment Review latest Structural	Via Drone       (typ 3 s photos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed       Via Drone (at least 2 photos) taken directly above the structure center, encompassing the complete site)         Completed       Completed         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Completed       Image: taken directly above the structure center, encompassing the complete site)         Ves       No         Ves       No         Are all antenna included in the Structural assessment?         Comments:       Image: taken directly above the structural assessment?				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate All RF feeders are <u>labelled</u> at the gland plate & antenna connection Is there a Geotechnical assessment Review latest Structural assessment	Via Drone (typ 3 Sphotos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed         Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site) Completed         Completed         Type of cable support fitted         Yes         Yes         No         Yes         Are all antenna included in the Structural assessment?				
Photograph each tower face and tower leg Photograph the overall site layout Photograph the cable ladder Photograph the gland plate All RF feeders are labelled at the gland plate & antenna connection Is there a Geotechnical assessment Review latest Structural assessment Tower Sienaee	Via Drone (typ 3 sphotos progressing up the face including photos showing the complete face to allow scaling of antenna heights).         Completed         Via Drone (at least 2 photos taken directly above the structure center, encompassing the complete site) Completed         Completed         Type of cable support fitted []         Completed         Yes         Yes         No         Yes         Are all <u>antenna</u> included in the Structural assessment?         Comments:         Photograph all fitted signs				



Venetation	Any astrong a lastroight human human
vegetation	Any antenna obstructed by hearby trees
obstruction	Yes 🗆 (photograph) No 🗖
	Measure the vegetation heights for the closest trees in each cardinal direction
	N
Aviation	Yes 🗆 No 🗖
warning lights	Comments:
fitted.	
Power Feed:	

#### POWER SYSTEMS

AC FEED TO SITE	1P / 3 Ph	11 KV Transformer spotted
	Meter Details:	Photograph
	Photograph	
SOLAR PANELS	Type: Qty: Array Size: Regulator Details: (Photograph all)	
GENERATOR	Туре:	
	Details:	
	Mtce records:	
	Photograph:	
	Last Started:	
	Photograph	
BATTERIES	Type: Strings: Total number: Date into service: Tested: Photograph	
OTHER (Wind, Fuel Cells, Water)		



Notes / Sketches



## Conclusions

www.satpty.com

Consider Value engineering, right sizing, conservatism costs, lack of considering the full Engineering design can be costly particularly with
regard to the Access, Power and Structural costs. easily able to blow out to typically 10x the Radio Network costs. This usually dominates
the cost expectations for a network rollout

#### **POWER ON SITE**

- Reduce equipment dimensioning (functionality (trunking example), Erlang capacity calculations, consumption, cooling requirement), think about scalable upgrades when you need
- How can we reduce Power footprints (passive cooling, double skins, out of the sun external placement, external heat sink, minimising kVA's of cooling, smart approach to Battery charging or generator operation)
- Strip back unnecessary equipment loads (lights, cold standby)
- With Solar systems equate the Total Lifecycle Cost (x years), in terms of expectation of kWHr

#### TOWER LOADING

- Reducing antenna footprints and size with technology
- Dropping height where possible, using logical locations for access
- Leasing space rather than Own and operate

### TOWER BUILDING

- Survey site and confirm important parameters, (access, height required, antenna table to enable tower specification), use template
- Understand Geology (Geotech report), site layout restrictions (Parks, Heritage, boundary, footprint)

### REAL ESTATE FOOTPRINT AND LOADING

- Reducing real estate footprints and volume
- Consider the lease model rather than site/tower own and operate

PROPERLY SURVEY THE SITE AND CAPTURE ALL THE RISKS, CAVEATS, PARAMETERS